

---

**To:** Helis Oil & Gas, LLC  
**From:** Kristjan Varnik, Tetra Tech  
**Subject:** Noise Monitoring Report Update (July 19-25, 2016)  
**Date:** July 26, 2016

---

Helis Oil & Gas, LLC has contracted Tetra Tech to provide environmental monitoring during exploration and development activities in St. Tammany Parish, Louisiana. This memo provides information on acoustic monitoring for the period between July 19<sup>th</sup> and July 26<sup>th</sup>. Drilling activities were initiated on June 29<sup>th</sup> at 2:00 pm Central Daylight Time and continued throughout the monitoring period. *The acoustic monitoring stations did not detect any significant differences in noise levels during periods of active drilling compared with the pre-drilling baseline period.*

Noise monitoring was conducted at two discrete locations per permit requirements. Site 1 is at the intersection of Interstate 12 and LA Highway 1088 (Figure 1). Site 2 is at Lakeshore High School. (Figure 2). The monitoring stations were set up within the fenced-in air monitoring areas for safety, maintenance access, security and robustness. Traffic noise, local vehicle noise, air quality monitors and air conditioners were the dominant anthropogenic sound sources at Site 1. Ambient noise generated by air handling equipment was discernable at the monitoring sites evaluated at Site 2. To reduce the influence of near-by noise, the ground level acoustic monitoring station was positioned adjacent to the equipment shed to best shield unwanted noise from the air monitoring equipment and auxiliary equipment. However, extraneous noise effects related to the air quality monitoring station within the fenced in area were removed from the data analysis for the purposes of this assessment.



**Figure 1. Acoustic monitoring at Site 1**



**Figure 2. Acoustic Monitoring at Site 2**

Measurements were taken with a Larson Davis 831 real-time sound level analyzer equipped with a PCB model 377B02 1/2" precision condenser microphone. This instrument has an operating range of 5 dB to 140 dB, and an overall frequency range of 8 to 20,000 Hz. It meets or exceeds all requirements in the American National Standards Institute (ANSI) standards for Type 1 sound level meters for quality and accuracy (precision). The sound meters are Larson Davis 831 Sound level meters connected to a portable PC with internet connectivity. Sound levels and equipment status are remotely monitored over the internet. The microphones and windscreens were tripod-mounted at an approximate height of 1.5 to 1.7 meters (4.9



to 5.6 feet) above grade away from effects of ground level noise and reflective surfaces. The calibration sheets of the equipment are included in Appendix A.

### Summary of Sound Levels (July 19th-26th, 2016)

Sound levels remained below 60 dBA for most of the period. Local increases were due to nearby traffic, air conditioning equipment, air quality monitoring equipment, aircraft flyovers or natural sounds. At both sites, the air quality monitors were activate every 3 days for 12 hour periods. Sound levels were slightly elevated Thursday July 21<sup>st</sup>, Friday July 22<sup>nd</sup>, and Monday July 25<sup>th</sup> as short precipitation events occurred on these days, with nearby thunderstorms.

#### Site 1 – Intersection of I-12 and LA 1088

At Site 1, vehicles, an air conditioner, on-site activities and air quality monitoring stations were the nearby noise sources. Sound levels were slightly elevated Thursday July 21<sup>st</sup>, Friday July 22<sup>nd</sup>, and Monday July 25<sup>th</sup> as short precipitation events occurred on these days.




Figure 3. Measured Sound Levels at Site 1 (July 19th – 25th, 2016)

#### Site 2 – Lakeshore High School

Sound levels were generally below 60 dB during the monitoring period. Air quality monitors are responsible for the increase in sounds every 3 days. The sound monitoring station was located near a parking lot, so occasional nearby vehicle traffic increased the measured sound levels. Flyovers from aircraft were also detected. Sound levels were slightly elevated Thursday July 21<sup>st</sup>, Friday July 22<sup>nd</sup>, and Monday July 25<sup>th</sup> as short precipitation events occurred on these days.




Figure 4. Measured Sound Levels at Site 2 (July 19th – 25th, 2016)



# Appendix A

## Measurement Equipment & NIST Laboratory Calibration Certifications

Helis Oil & Gas - Noise Monitoring



# Calibration Certificate

**Certificate Number** 2015001436

**Customer:**

Hilton Garden Inn Covington/Mandeville  
350 Holiday Square Boulevard  
Covington, LA 70433, United States

**Model Number** 831  
**Serial Number** 0003847  
**Test Results** **Pass**

**Initial Condition** As Manufactured

**Description** Larson Davis Model 831

**Procedure Number** D0001.8378

**Technician** Ron Harris

**Calibration Date** 16 Feb 2015

**Calibration Due**

**Temperature** 23.06 °C ± 0.01 °C

**Humidity** 50.1 %RH ± 0.5 %RH

**Static Pressure** 86.43 kPa ± 0.03 kPa

**Evaluation Method** Tested electrically using PRM831 S/N 036754 and a 12.0 pF capacitor to simulate microphone capacitance. Data reported in dB re 20 µPa assuming a microphone sensitivity of 50.0 mV/Pa.

**Compliance Standards** Compliant to Manufacturer Specifications and the following standards when combined with Calibration Certificate from procedure D0001.8384:

IEC 60651:2001 Type 1	ANSI S1.4-2014 Class 1
IEC 60804:2000 Type 1	ANSI S1.4 (R2006) Type 1
IEC 61252:2002	ANSI S1.11 (R2009) Class 1
IEC 61260:2001 Class 1	ANSI S1.25 (R2007)
IEC 61672:2013 Class 1	ANSI S1.43 (R2007) Type 1

Issuing lab certifies that the instrument described above meets or exceeds all specifications as stated in the referenced procedure (unless otherwise noted). It has been calibrated using measurement standards traceable to the SI through the National Institute of Standards and Technology (NIST), or other national measurement institutes, and meets the requirements of ISO/IEC 17025:2005.

**Test points marked with a ‡ in the uncertainties column do not fall within this laboratory's scope of accreditation.**

The quality system is registered to ISO 9001:2008.

This calibration is a direct comparison of the unit under test to the listed reference standards and did not involve any sampling plans to complete. No allowance has been made for the instability of the test device due to use, time, etc. Such allowances would be made by the customer as needed.

The uncertainties were computed in accordance with the ISO Guide to the Expression of Uncertainty in Measurement (GUM). A coverage factor of approximately 2 sigma (k=2) has been applied to the standard uncertainty to express the expanded uncertainty at approximately 95% confidence level.

This report may not be reproduced, except in full, unless permission for the publication of an approved abstract is obtained in writing from the organization issuing this report.

## Standards Used


Description	Cal Date	Cal Due	Cal Standard
SRS DS360 Ultra Low Distortion Generator	02/06/2015	02/06/2016	006239
Hart Scientific 2626-S Humidity/Temperature Sensor	05/16/2014	05/16/2015	006943

Larson Davis, a division of PCB Piezotronics, Inc  
1681 West 820 North  
Provo, UT 84601, United States  
716-684-0001





## Z-weight Filter Response




Electrical signal test of frequency weighting performed according to IEC 61672-3:2013 13 and ANSI S1.4-2014 Part 3: 13 for compliance to IEC 61672-1:2013 5.5; IEC 60651:2001 6.1 and 9.2.2; IEC 60804:2000 5; ANSI S1.4:1983 (R2006) 5.1 and 8.2.1; ANSI S1.4-2014 Part 1: 5.5

Frequency [Hz]	Test Result [dB]	Error [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
6.31	-0.43	-0.43	-0.63	0.12	0.10	Pass
1,000.00	0.00	0.00	-0.30	0.30	0.09	Pass
19,952.62	-0.37	-0.37	-0.71	0.41	0.09	Pass
-- End of measurement results--						



## A-weighted Broadband Log Linearity: 8,000.00 Hz



Broadband level linearity with 0 dB gain performed according to IEC 61672-3:2013 16 and ANSI S1.4-2014 Part 3: 16 for compliance to IEC 61672-1:2013 5.6, IEC 60804:2000 6.2, IEC 61252:2002 8, ANSI S1.4 (R2006) 6.9, ANSI S1.4-2014 Part 1: 5.6, ANSI S1.43 (R2007) 6.2

Level [dB]	Error [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
31.00	0.05	-0.70	0.70	0.09	Pass
32.00	0.11	-0.70	0.70	0.09	Pass
33.00	0.00	-0.70	0.70	0.09	Pass
34.00	0.04	-0.70	0.70	0.09	Pass
35.00	0.01	-0.70	0.70	0.09	Pass
36.00	0.01	-0.70	0.70	0.09	Pass
39.00	0.03	-0.70	0.70	0.09	Pass
44.00	0.00	-0.70	0.70	0.09	Pass
49.00	0.00	-0.70	0.70	0.09	Pass
54.00	0.00	-0.70	0.70	0.09	Pass
59.00	0.00	-0.70	0.70	0.09	Pass
64.00	0.01	-0.70	0.70	0.09	Pass
69.00	0.01	-0.70	0.70	0.09	Pass
74.00	0.03	-0.70	0.70	0.09	Pass
79.00	0.01	-0.70	0.70	0.09	Pass
84.00	0.02	-0.70	0.70	0.09	Pass
89.00	0.02	-0.70	0.70	0.09	Pass
94.00	0.02	-0.70	0.70	0.09	Pass
99.00	0.02	-0.70	0.70	0.09	Pass
104.00	0.01	-0.70	0.70	0.09	Pass
109.00	0.01	-0.70	0.70	0.09	Pass
114.00	-0.01	-0.70	0.70	0.09	Pass
119.00	-0.05	-0.70	0.70	0.09	Pass
124.00	-0.04	-0.70	0.70	0.09	Pass
129.00	-0.03	-0.70	0.70	0.09	Pass
134.00	-0.02	-0.70	0.70	0.09	Pass
135.00	-0.02	-0.70	0.70	0.09	Pass
136.00	-0.01	-0.70	0.70	0.09	Pass
137.00	-0.01	-0.70	0.70	0.09	Pass
138.00	-0.01	-0.70	0.70	0.09	Pass
139.00	-0.01	-0.70	0.70	0.09	Pass
140.00	-0.01	-0.70	0.70	0.09	Pass

-- End of measurement results--



### Rise Time

Peak rise time performed according to IEC 60651:2001 9.4.4 and ANSI S1.4:1983 (R2006) 8.4.4

Amplitude [dB]	Duration [μs]		Test Result [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
137.00	40	Negative Pulse	135.91	134.55	136.55	0.09	Pass
		Positive Pulse	135.97	134.51	136.51	0.09	Pass
	30	Negative Pulse	135.06	134.55	136.55	0.09	Pass
		Positive Pulse	135.02	134.51	136.51	0.09	Pass

-- End of measurement results--

### Positive Pulse Crest Factor

#### 200 μs pulse tests at 2.0, 12.0, 22.0, 32.0 dB below Overload Limit

Crest Factor measured according to IEC 60651:2001 9.4.2 and ANSI S1.4:1983 (R2006) 8.4.2

Amplitude [dB]	Crest Factor	Test Result [dB]	Limits [dB]	Expanded Uncertainty [dB]	Result
138.00	3	OVLD	± 0.50	0.09	Pass
	5	OVLD	± 1.00	0.09	Pass
	10	OVLD	± 1.50	0.09	Pass
128.00	3	-0.09	± 0.50	0.10	Pass
	5	-0.07	± 1.00	0.09	Pass
	10	OVLD	± 1.50	0.09	Pass
118.00	3	-0.09	± 0.50	0.10	Pass
	5	-0.09	± 1.00	0.09	Pass
	10	-0.15	± 1.50	0.09	Pass
108.00	3	-0.09	± 0.50	0.13	Pass
	5	-0.09	± 1.00	0.09	Pass
	10	-0.23	± 1.50	0.09	Pass

-- End of measurement results--



**Negative Pulse Crest Factor****200  $\mu$ s pulse tests at 2.0, 12.0, 22.0, 32.0 dB below Overload Limit**

Crest Factor measured according to IEC 60651:2001 9.4.2 and ANSI S1.4:1983 (R2006) 8.4.2

Amplitude [dB]	Crest Factor	Test Result [dB]	Limits [dB]	Expanded Uncertainty [dB]	Result
138.00	3	OVLD	$\pm 0.50$	0.09	Pass
	5	OVLD	$\pm 1.00$	0.09	Pass
	10	OVLD	$\pm 1.50$	0.09	Pass
128.00	3	-0.06	$\pm 0.50$	0.09	Pass
	5	-0.07	$\pm 1.00$	0.09	Pass
	10	OVLD	$\pm 1.50$	0.09	Pass
118.00	3	-0.08	$\pm 0.50$	0.10	Pass
	5	-0.06	$\pm 1.00$	0.09	Pass
	10	-0.12	$\pm 1.50$	0.09	Pass
108.00	3	-0.06	$\pm 0.50$	0.09	Pass
	5	-0.06	$\pm 1.00$	0.09	Pass
	10	-0.18	$\pm 1.50$	0.09	Pass

-- End of measurement results--

**Gain**

Gain measured according to IEC 61672-3:2013 17.3 and 17.4 and ANSI S1.4-2014 Part 3: 17.3 and 17.4


Measurement	Test Result [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
Normal Range	93.56	93.20	94.80	0.09	Pass
Low Range	93.57	93.46	93.66	0.09	Pass
20 dB Gain	93.57	93.46	93.66	0.09	Pass
20 dB Gain, Linearity	24.11	23.86	25.26	0.22	Pass

-- End of measurement results--





## 1/3-Octave Self-Generated Noise



The SLM is set to low range and 0 dB gain. 1/3-Octave self-generated noise measured according to IEC 61672-3:2013 11.2 and ANSI S1.4-2014 Part 3: 11.2

Frequency [Hz]	Test Result [dB]	Upper limit [dB]	Result
6.30	11.46	15.50	Pass
8.00	11.15	14.70	Pass
10.00	9.66	13.90	Pass
12.50	8.88	13.10	Pass
16.00	7.23	12.30	Pass
20.00	6.24	11.50	Pass
25.00	4.82	10.70	Pass
31.50	3.83	9.90	Pass
40.00	3.17	9.10	Pass
50.00	2.24	8.10	Pass
63.00	1.68	7.10	Pass
80.00	0.34	6.10	Pass
100.00	0.12	5.30	Pass
125.00	-0.70	4.70	Pass
160.00	-1.67	4.10	Pass
200.00	-2.09	3.60	Pass
250.00	-2.65	3.10	Pass
315.00	-2.83	2.70	Pass
400.00	-2.50	2.60	Pass
500.00	-3.52	2.60	Pass
630.00	-3.70	2.70	Pass
800.00	-3.28	2.80	Pass
1,000.00	-3.15	3.00	Pass
1,250.00	-2.77	3.20	Pass
1,600.00	-2.13	3.50	Pass
2,000.00	-1.48	3.80	Pass
2,500.00	-0.80	4.30	Pass
3,150.00	0.16	4.90	Pass
4,000.00	1.00	5.70	Pass
5,000.00	2.03	6.40	Pass
6,300.00	2.95	7.40	Pass
8,000.00	3.78	8.60	Pass
10,000.00	4.81	9.80	Pass
12,500.00	5.99	11.20	Pass
16,000.00	6.77	12.60	Pass

Larson Davis, a division of PCB Piezotronics, Inc  
 1681 West 820 North  
 Provo, UT 84601, United States  
 716-684-0001



**LARSON DAVIS**  
 A PCB PIEZOTRONICS DIV.



Frequency [Hz]	Test Result [dB]	Upper limit [dB]	Result
20,000.00	8.15	14.00	Pass

-- End of measurement results--

**Broadband Noise Floor**

Self-generated noise measured according to IEC 61672-3:2013 11.2 and ANSI S1.4-2014 Part 3: 11.2

Measurement	Test Result [dB]	Upper limit [dB]	Result
A-weight Noise Floor	12.81	15.00	Pass
C-weight Noise Floor	14.59	17.30	Pass
Z-weight Noise Floor	22.73	24.50	Pass

-- End of measurement results--

**Total Harmonic Distortion**

Measured using 1/3-Octave filters

Measurement	Test Result [dB]	Lower Limit [dB]	Upper Limit [dB]	Expanded Uncertainty [dB]	Result
10 Hz Signal	137.51	137.20	138.80	0.09	Pass
THD	-72.49		-60.00	0.01	Pass
THD+N	-65.96		-60.00	0.01	Pass

-- End of measurement results--

-- End of Report--

Signatory: Ron Harris

Larson Davis, a division of PCB Piezotronics, Inc  
 1681 West 820 North  
 Provo, UT 84601, United States  
 716-684-0001



**LARSON DAVIS**  
 A PCB PIEZOTRONICS DIV.



# Calibration Certificate

**Certificate Number** 2015001435

**Customer:**

Hilton Garden Inn Covington/Mandeville  
350 Holiday Square Boulevard  
Covington, LA 70433, United States

**Model Number** 831  
**Serial Number** 0003848  
**Test Results** **Pass**

**Initial Condition** As Manufactured

**Description** Larson Davis Model 831

**Procedure Number** D0001.8378  
**Technician** Ron Harris  
**Calibration Date** 16 Feb 2015

**Calibration Due**  
**Temperature** 23.07 °C ± 0.01 °C  
**Humidity** 49.5 %RH ± 0.5 %RH  
**Static Pressure** 86.43 kPa ± 0.03 kPa

**Evaluation Method** Tested electrically using PRM831 S/N 036755 and a 12.0 pF capacitor to simulate microphone capacitance. Data reported in dB re 20 µPa assuming a microphone sensitivity of 50.0 mV/Pa.

**Compliance Standards** Compliant to Manufacturer Specifications and the following standards when combined with Calibration Certificate from procedure D0001.8384:

IEC 60651:2001 Type 1	ANSI S1.4-2014 Class 1
IEC 60804:2000 Type 1	ANSI S1.4 (R2006) Type 1
IEC 61252:2002	ANSI S1.11 (R2009) Class 1
IEC 61260:2001 Class 1	ANSI S1.25 (R2007)
IEC 61672:2013 Class 1	ANSI S1.43 (R2007) Type 1

Issuing lab certifies that the instrument described above meets or exceeds all specifications as stated in the referenced procedure (unless otherwise noted). It has been calibrated using measurement standards traceable to the SI through the National Institute of Standards and Technology (NIST), or other national measurement institutes, and meets the requirements of ISO/IEC 17025:2005.

**Test points marked with a ‡ in the uncertainties column do not fall within this laboratory's scope of accreditation.**

The quality system is registered to ISO 9001:2008.

This calibration is a direct comparison of the unit under test to the listed reference standards and did not involve any sampling plans to complete. No allowance has been made for the instability of the test device due to use, time, etc. Such allowances would be made by the customer as needed.

The uncertainties were computed in accordance with the ISO Guide to the Expression of Uncertainty in Measurement (GUM). A coverage factor of approximately 2 sigma (k=2) has been applied to the standard uncertainty to express the expanded uncertainty at approximately 95% confidence level.

This report may not be reproduced, except in full, unless permission for the publication of an approved abstract is obtained in writing from the organization issuing this report.

## Standards Used


Description	Cal Date	Cal Due	Cal Standard
Hart Scientific 2626-S Humidity/Temperature Sensor	05/16/2014	05/16/2015	006943
SRS DS360 Ultra Low Distortion Generator	11/13/2014	11/13/2015	007167

Larson Davis, a division of PCB Piezotronics, Inc  
1681 West 820 North  
Provo, UT 84601, United States  
716-684-0001





## Z-weight Filter Response




Electrical signal test of frequency weighting performed according to IEC 61672-3:2013 13 and ANSI S1.4-2014 Part 3: 13 for compliance to IEC 61672-1:2013 5.5; IEC 60651:2001 6.1 and 9.2.2; IEC 60804:2000 5; ANSI S1.4:1983 (R2006) 5.1 and 8.2.1; ANSI S1.4-2014 Part 1: 5.5

Frequency [Hz]	Test Result [dB]	Error [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
6.31	-0.32	-0.32	-0.63	0.12	0.09	Pass
1,000.00	0.00	0.00	-0.30	0.30	0.09	Pass
19,952.62	-0.20	-0.20	-0.71	0.41	0.09	Pass

-- End of measurement results--



## A-weighted Broadband Log Linearity: 8,000.00 Hz



Broadband level linearity with 0 dB gain performed according to IEC 61672-3:2013 16 and ANSI S1.4-2014 Part 3: 16 for compliance to IEC 61672-1:2013 5.6, IEC 60804:2000 6.2, IEC 61252:2002 8, ANSI S1.4 (R2006) 6.9, ANSI S1.4-2014 Part 1: 5.6, ANSI S1.43 (R2007) 6.2

Level [dB]	Error [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
31.00	0.14	-0.70	0.70	0.09	Pass
32.00	0.09	-0.70	0.70	0.09	Pass
33.00	0.08	-0.70	0.70	0.09	Pass
34.00	0.07	-0.70	0.70	0.09	Pass
35.00	0.04	-0.70	0.70	0.09	Pass
36.00	0.05	-0.70	0.70	0.09	Pass
39.00	0.06	-0.70	0.70	0.09	Pass
44.00	0.03	-0.70	0.70	0.09	Pass
49.00	0.02	-0.70	0.70	0.09	Pass
54.00	0.02	-0.70	0.70	0.09	Pass
59.00	0.02	-0.70	0.70	0.09	Pass
64.00	0.00	-0.70	0.70	0.09	Pass
69.00	0.01	-0.70	0.70	0.09	Pass
74.00	-0.01	-0.70	0.70	0.09	Pass
79.00	0.03	-0.70	0.70	0.09	Pass
84.00	0.01	-0.70	0.70	0.09	Pass
89.00	0.01	-0.70	0.70	0.09	Pass
94.00	0.01	-0.70	0.70	0.09	Pass
99.00	0.01	-0.70	0.70	0.09	Pass
104.00	-0.02	-0.70	0.70	0.09	Pass
109.00	0.02	-0.70	0.70	0.09	Pass
114.00	0.00	-0.70	0.70	0.09	Pass
119.00	0.03	-0.70	0.70	0.09	Pass
124.00	0.02	-0.70	0.70	0.09	Pass
129.00	0.02	-0.70	0.70	0.09	Pass
134.00	0.02	-0.70	0.70	0.09	Pass
135.00	0.01	-0.70	0.70	0.09	Pass
136.00	0.02	-0.70	0.70	0.09	Pass
137.00	0.01	-0.70	0.70	0.09	Pass
138.00	0.01	-0.70	0.70	0.09	Pass
139.00	0.01	-0.70	0.70	0.09	Pass
140.00	0.01	-0.70	0.70	0.09	Pass

-- End of measurement results--



### Rise Time

Peak rise time performed according to IEC 60651:2001 9.4.4 and ANSI S1.4:1983 (R2006) 8.4.4

Amplitude [dB]	Duration [μs]		Test Result [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
137.00	40	Negative Pulse	136.02	134.51	136.51	0.09	Pass
		Positive Pulse	136.02	134.51	136.51	0.09	Pass
	30	Negative Pulse	135.06	134.51	136.51	0.09	Pass
		Positive Pulse	135.07	134.51	136.51	0.09	Pass

-- End of measurement results--

### Positive Pulse Crest Factor

#### 200 μs pulse tests at 2.0, 12.0, 22.0, 32.0 dB below Overload Limit

Crest Factor measured according to IEC 60651:2001 9.4.2 and ANSI S1.4:1983 (R2006) 8.4.2

Amplitude [dB]	Crest Factor		Test Result [dB]	Limits [dB]	Expanded Uncertainty [dB]	Result
138.00	3		OVLD	± 0.50	0.09	Pass
	5		OVLD	± 1.00	0.09	Pass
	10		OVLD	± 1.50	0.09	Pass
128.00	3		-0.13	± 0.50	0.10	Pass
	5		-0.12	± 1.00	0.09	Pass
	10		OVLD	± 1.50	0.09	Pass
118.00	3		-0.13	± 0.50	0.10	Pass
	5		-0.12	± 1.00	0.09	Pass
	10		-0.16	± 1.50	0.09	Pass
108.00	3		-0.13	± 0.50	0.13	Pass
	5		-0.12	± 1.00	0.09	Pass
	10		-0.26	± 1.50	0.09	Pass

-- End of measurement results--



**Negative Pulse Crest Factor****200  $\mu$ s pulse tests at 2.0, 12.0, 22.0, 32.0 dB below Overload Limit**

Crest Factor measured according to IEC 60651:2001 9.4.2 and ANSI S1.4:1983 (R2006) 8.4.2

Amplitude [dB]	Crest Factor	Test Result [dB]	Limits [dB]	Expanded Uncertainty [dB]	Result
138.00	3	OVLD	$\pm 0.50$	0.09	Pass
	5	OVLD	$\pm 1.00$	0.09	Pass
	10	OVLD	$\pm 1.50$	0.09	Pass
128.00	3	-0.12	$\pm 0.50$	0.09	Pass
	5	-0.12	$\pm 1.00$	0.09	Pass
	10	OVLD	$\pm 1.50$	0.09	Pass
118.00	3	-0.12	$\pm 0.50$	0.09	Pass
	5	-0.12	$\pm 1.00$	0.09	Pass
	10	-0.16	$\pm 1.50$	0.09	Pass
108.00	3	-0.12	$\pm 0.50$	0.09	Pass
	5	-0.12	$\pm 1.00$	0.09	Pass
	10	-0.26	$\pm 1.50$	0.09	Pass
-- End of measurement results--					


**Gain**

Gain measured according to IEC 61672-3:2013 17.3 and 17.4 and ANSI S1.4-2014 Part 3: 17.3 and 17.4

Measurement	Test Result [dB]	Lower limit [dB]	Upper limit [dB]	Expanded Uncertainty [dB]	Result
Normal Range	93.59	93.20	94.80	0.09	Pass
Low Range	93.60	93.49	93.69	0.09	Pass
20 dB Gain	93.59	93.49	93.69	0.09	Pass
20 dB Gain, Linearity	24.24	23.89	25.29	0.29	Pass
-- End of measurement results--					



## 1/3-Octave Self-Generated Noise



The SLM is set to low range and 0 dB gain. 1/3-Octave self-generated noise measured according to IEC 61672-3:2013 11.2 and ANSI S1.4-2014 Part 3: 11.2

Frequency [Hz]	Test Result [dB]	Upper limit [dB]	Result
6.30	10.46	15.50	Pass
8.00	10.85	14.70	Pass
10.00	8.94	13.90	Pass
12.50	8.42	13.10	Pass
16.00	7.20	12.30	Pass
20.00	7.14	11.50	Pass
25.00	5.56	10.70	Pass
31.50	4.52	9.90	Pass
40.00	3.67	9.10	Pass
50.00	2.95	8.10	Pass
63.00	2.25	7.10	Pass
80.00	0.80	6.10	Pass
100.00	-0.26	5.30	Pass
125.00	-0.43	4.70	Pass
160.00	-1.58	4.10	Pass
200.00	-2.07	3.60	Pass
250.00	-2.83	3.10	Pass
315.00	-2.73	2.70	Pass
400.00	-3.13	2.60	Pass
500.00	-3.58	2.60	Pass
630.00	-3.54	2.70	Pass
800.00	-3.34	2.80	Pass
1,000.00	-3.15	3.00	Pass
1,250.00	-2.72	3.20	Pass
1,600.00	-2.14	3.50	Pass
2,000.00	-1.49	3.80	Pass
2,500.00	-0.75	4.30	Pass
3,150.00	0.15	4.90	Pass
4,000.00	1.12	5.70	Pass
5,000.00	2.00	6.40	Pass
6,300.00	2.87	7.40	Pass
8,000.00	3.68	8.60	Pass
10,000.00	4.71	9.80	Pass
12,500.00	5.77	11.20	Pass
16,000.00	6.75	12.60	Pass

Larson Davis, a division of PCB Piezotronics, Inc  
 1681 West 820 North  
 Provo, UT 84601, United States  
 716-684-0001



**LARSON DAVIS**  
 A PCB PIEZOTRONICS DIV.



Frequency [Hz]	Test Result [dB]	Upper limit [dB]	Result
20,000.00	8.13	14.00	Pass

-- End of measurement results--

**Broadband Noise Floor**

Self-generated noise measured according to IEC 61672-3:2013 11.2 and ANSI S1.4-2014 Part 3: 11.2

Measurement	Test Result [dB]	Upper limit [dB]	Result
A-weight Noise Floor	12.75	15.00	Pass
C-weight Noise Floor	14.68	17.30	Pass
Z-weight Noise Floor	23.05	24.50	Pass

-- End of measurement results--

**Total Harmonic Distortion**

Measured using 1/3-Octave filters

Measurement	Test Result [dB]	Lower Limit [dB]	Upper Limit [dB]	Expanded Uncertainty [dB]	Result
10 Hz Signal	137.53	137.20	138.80	0.09	Pass
THD	-74.36		-60.00	0.01	Pass
THD+N	-66.78		-60.00	0.01	Pass

-- End of measurement results--

-- End of Report--

Signatory: Ron Harris

Larson Davis, a division of PCB Piezotronics, Inc  
 1681 West 820 North  
 Provo, UT 84601, United States  
 716-684-0001

