ADDENDUM 02 TO BID DOCUMENTS FOR

LIVING SHORELINE DEMONSTRATION PROJECT (PO-148)

ST. BERNARD PARISH, LOUISIANA







STATE OF LOUISIANA COASTAL PROTECTION AND RESTORATION AUTHORITY

OCTOBER 29, 2015



ADDENDUM 02 TO BID DOCUMENTS LIVING SHORELINE DEMONSTRATION PROJECT (PO-148)

The clarifications and revisions in this addendum supersede the requirements in the Bid Documents dated September 2015. The Successful bidder will be issued a complete revised set of plans and specifications.

1. PRE-BID MEETING SIGN-IN SHEETS

The Mandatory Pre-Bid Conference Attendance Record is provided in Attachment A.

2. RESPONSE TO CONTRACTOR QUESTIONS

2.1. QUESTION: Would it be possible to obtain a copy of the attendee list for Tuesday's prebid meeting for PO-0148, the Living Shoreline Demonstration Project.

ANSWER: The Mandatory Pre-Bid Conference Attendance Record is provided in Attachment A.

2.2. QUESTION: Will there be payment for stored materials once manufacturers are at critical milestones in their production?

ANSWER: See Addendum 2 Item 3.7 below.

2.3. QUESTION: Due to the sole sourcing nature of the manufactured product, could CPRA require the manufacturers to bond their portion of the work?

ANSWER: Requirements for bid security, performance, and payment bonds for this Project are set forth in the Bid Documents, including but not limited to, Article 5.2 and Article 8 of the Instructions to Bidders.

2.4. QUESTION: Can the manufacturers be forced to agree to liquidated damages if they don't hit their schedule?

ANSWER: The Contractor shall be responsible to the Owner for the performance of the work and the use and coordination of trades and subcontractors in accordance with all terms and conditions contained in the Bid Documents, including but not limited to, GP-19, GP-20, and GP-31.

2.5. QUESTION: Will the manufacturer's pricing to the contractors be made public?

ANSWER: The manufacturer has provided a statement of pricing that is available in Appendix G of the Bid Documents.

2.6. QUESTION: Is it possible to provide pricing for the biologist on a weekly or daily

basis? There is a chance that the biologist could be on site for the initial two weeks prior to beginning deployment and not be needed for the rest of the project. On the other hand he may be needed for the entire duration of deployment.

ANSWER: Payment for all requirements of TS-6 will be as stated in TS-6.11.

2.7. QUESTION: The permanent navigation aid. Pipe Pile coating. How much of the pipe is required to be coated? Does the inside wall of the pipe require coating as well?

ANSWER: See Addendum 2 Items 3.18 and 3.19 below.

2.8. QUESTION: Wanted to follow up on last Tuesday Meetings with finding a way to pay for stored deliverables. LSS would have to commit \$1.3-1.7 million in manufacturing and delivery of all the required WADs for Base bid and alternate bids many months before getting any return. We would be at mercy of getting paid until deployment contractor got them in the water. We are a small business and know that other contractors will be unable to participate because of this. As we discussed. We recommend that WADs and other products get inspected and accepted at storage facility or mobilization site awaiting deployment. When accepted by your engineers, then we can invoice and receive a significant % of the total with the final percentage paid at completion of project. This has been done for several similar projects we have done in the State. Thanking you in advance for your consideration on this.

ANSWER: See Addendum 2 Item 3.7 below.

2.9. QUESTION: If there is not a provision added for stored materials, what is the receipt of funds expected to be in an approved billing cycle?

ANSWER: See Addendum 2 Item 3.7 below.

2.10.QUESTION: The stored materials billing cycle for contractors is going to be based on what timeline? Once a month, every two weeks?

ANSWER: Request for payment for stored materials per Addendum 2 Item 3.7 below shall be part of contractors application for payment per GP-59.

2.11.QUESTION: The Living Shoreline Demonstration Project mentions in the specs that the project requires a qualified biologist familiar with protected birds. I was wondering if you could provide contact information for a few such biologists.

ANSWER: See TS-6.8.2.1 for requirements for qualified biologists. CPRA is precluded from recommending a specific biologist or firm.

2.12.QUESTION: The spec for the navigation aids are the Tideland L-120 Self-contained 2NM lantern, Tideland is strongly suggesting using the SolaMax-3 as it the latest version of the L-120.

ANSWER: Navigation aid light shall remain as specified in TS-13 and Plan Sheet 29.

2.13.QUESTION: We believe that specs listed for WAD were pulled from a form fabricators drawing that were submitted for discussion purposes but weights and wall thickness were pulled from that sample drawing. We submitted official spec via a TS-8 submittal. Respectfully request that paragraph 10.5.2 be changed to reflect Unit weight: Greater than or equal to 7200 lbs. and less than 9150 lbs. additional request 10.5.1.1 be changed to reflect a minimum 4" wall thickness as per submitted TS-8. I believe the numbers reflected were pulled from a sample engineering drawing of one of our fabricators. We had no WAD weights presented in our submitted TS-8 Coastal Haven Spec.

ANSWER: Please see Addendum 2 Items 3.11, 3.12, and 4.1.

2.14.QUESTION: Can paragraph 7.9.2, under 7.9 Temporary Navigation Aid (page 76 of 137) be clarified? Is the contractor responsible for obtaining a permit from the US Coast Guard and/or the US Army Corps of Engineers for all temporary dredging and disposal?

ANSWER: Please see Addendum 2 Item 3.8.

2.15.QUESTION: How will the state tax and local tax be applied or exempted for manufacturer's products, within the project?

ANSWER: Taxes will be treated as stated under GP-34.

2.16.QUESTION: How is the contractor supposed to determine which anchor to use. It is calling out that it's up to the contractor to select an anchor that will hold up to 5,000 psi depending on soil conditions. Shouldn't this be something the engineer should determine and spec out an anchor to be used?

ANSWER: Anchors must meet performance requirements as specified in TS-12.8 and on Plan Sheet 21. Results from a geotechnical investigation of the site are provided in Appendix E. Details of proposed anchoring must be submitted to Engineer per TS-12.2.1.10.

2.17. QUESTION: Can the bottom be disturbed while setting reef blocks? Using a marsh excavator to set these units.

ANSWER: The water bottom shall not be disturbed during access to the work area, other than that shown on the Plans. See TS-3.2, and for more detail, see Appendix F, Louisiana Coastal Use Permit condition 11.a.

2.18.QUESTION: The Geotextile Fabric (Table 1) has the Geogrid properties and the Geogrid (Table 2) has the properties for the Geotextile.

ANSWER: See Addendum 2 Item 3.9.

2.19. QUESTION: I have searched for a Geotextile that will meet the 15% Open area and have not been able to find one. Do you have an example of a product that will meet all of the properties in your spec? Also neither one of the tables list the test methods used for each property.

ANSWER: See Addendum 2 Item 3.9.

2.20. QUESTION: Please clarify if the determination to include or delete the performance of Alternate Bid Items will be made at the time of contract award.

ANSWER: 2. The Contractor will be notified of the accepted Alternate Bid Items when the Contract is awarded

2.21.QUESTION: Please allow payment for offsite materials. It seems the contract has provided ample owner assurance through the requirements to provide Payment & Performance Bonds as well as including a 5% retainage clause.

ANSWER: Request for payment for stored materials per Addendum 2 Item 3.7 below shall be part of contractors application for payment per GP-59.

2.22.QUESTION: The stated no work distances basically encompass the entire landside area between Lake Eloi and Eloi Bay which is adjacent to the Base Bid jobsite. This results in over 500 acres of area that would need to be patrolled twice daily whether or not the contractor is working. Will marsh buggies, air boats, mud boats or other equipment be allowed to traverse the land area adjacent to the Base and Alternate jobsites in order to perform the required patrolling?

ANSWER: No.

3. REVISIONS TO THE GENERAL PROVISIONS, SPECIAL PROVISIONS, AND TECHNICAL SPECIFICATIONS

Provision/Specification language modifications are **bolded** and inclusion and/or revision are shown in *italics*; deletions are show in *strikethrough*.

3.1. SP-6. ADDRESSES FOR DOCUMENT DELIVERY – the contact information for the CPRA Field Engineer shall be changed to the following:

CPRA Field Engineer David Chambers, PE 2045 Lakeshore Drive, *CERM Bldg*, Suite 309 New Orleans, LA 70122

Phone: (504) 280-**4069** Fax: (504) 280-4066

E-mail: David.Chambers@la.gov

3.2. SP-4. MILESTONES – the specification has been revised as follows (note: only rows with changes are shown in addendum):

| Milestone | Location or Recipient | Date Due | Specification |
|------------------|-----------------------|---|--------------------|
| Project Schedule | Engineer | 14 days prior to Preconstruction conference; updated and submitted at each Progress Meeting | GP-9 and SP-5.6 |

- 3.3. SP-5. DELIVERABLES, 5.7.2, has been revised as follows:
 - 5.7.2 Progress Schedule as specified in GP-9 and SP-5.6;
- 3.4. SP-5. DELIVERABLES, 5.8.2, has been revised as follows:
 - 5.8.2 Progress Schedule as specified in GP-9 and SP-5.6;
- 3.5. SP-5. DELIVERABLES, 5.12.4, has been revised as follows (note: only rows with changes are shown in addendum):
 - 5.12.4 The following table is a summary of submittals required of the Contractor as part of this section and other sections of these Specifications:

Table 1 Summary of Submittals

| Submittal | Location or Recipient | Date Due | Specification |
|--------------------------------|-----------------------|--|--|
| Progress Schedule | Engineer | 14 days prior to the Pre- Construction Conference | GP-9 and SP-5.6 |
| Work Plan and Schedule Updates | Engineer | Pre-Construction Conference | GP-9 and , <i>SP-5.6</i> , SP-7 |
| Progress Schedule | Engineer | During Construction; with every bi-weekly progress meeting | GP-9 and SP-5.6 |

- 3.6. SP-7. WORK PLAN SUPPLEMENTAL, 7.8, has been modified as follows
 - 7.8 Construction schedule per GP-9 and SP-5.6;
- 3.7. Add SP-28, as follow:

SP-28 PAYMENT FOR STORED MATERIALS

28.1 - General:

If approved by the Owner, payments may be made for stored material, limited to

manufactured artificial reef units, including Oysterbreak Units, WAD Units, Reef Ball Units, and ReefBLK Units, that will be incorporated into the project and which represent a significant portion of the project costs. Such material shall be stored on the project site or, with prior approval by the Owner, in a dedicated stockpile located at a site outside of the designated project site. Payments for stored material will be considered only for materials anticipated to be stored for periods in excess of 30 calendar days. All stored materials shall meet the requirements of the plans and specifications and the Owner reserves the right to inspect stored materials. Payment for stored materials does not constitute acceptance by the Owner. It shall be the Contractor's responsibility to protect the material from damage while in storage.

28.2 - Request and Payment:

Payment for stored materials will be based on the invoice price for the materials. The amounts advanced on stored materials will be recovered by the Owner through deductions made on payments as the materials are incorporated into the work. The quantity of material for payment shall not exceed sixty five percent (65%) of the total bid quantity for each artificial reef Bid Item required to complete the project (base and any awarded alternates).

Payment for stored materials shall be requested by the Contractor in writing with their monthly application for payment per GP-59 and the following shall also be furnished to the Owner:

- (1) A copy of the invoices from supplier or manufacturer verifying the cost and quantity of material; and
- (2) If the proposed storage is located on private property, a copy of the lease or agreement granting the Contractor permission to store materials on that site, including permission granting the Owner and Resident Project Representative right of entry to the property; and
- (3) An acknowledgement from the Contractor of his continuing risk of loss and written notice from the Contractor's surety indicating consent to payment for stored materials.

Within 30 calendar days after payment by the Owner, the contractor shall submit a certified copy of invoices from the supplier for each item for which payment has been made. All such invoices submitted shall state the amount received by the supplier as payment in full for the materials. If this certification of payment is not presented within the 30-day period, the advanced payment will be deducted from future progress payments.

All submittals shall be made in accordance with GP-41 and SP-5.

28.3 - Ownership:

Ownership of stored materials for which payment has been made shall not transfer to the Owner until such materials are incorporated into the work and the Owner has accepted the completed work. Payments issued by the Owner for stored materials pursuant to this Provision shall not release the Contractor from the responsibility for any portion thereto nor shall such payments relieve the Contractor from any other obligation contained in this

Contract.

- 3.8. TS-7 ACCESS AND FLOATATION CHANNELS, 7.9 Temporary Navigation Aids paragraph 7.9.2 has been revised as follows:
 - 7.9.2 The Contractor shall obtain a permit from the U.S. Coast Guard and/or the US Army Corps of Engineers for all temporary navigation aids required for temporary dredging and temporary disposal, or navigation aid markers to be placed in the water prior to construction in the vicinity of the temporary disposal site and other works for the duration (and at any point during the performance) of the construction work.
- 3.9. TS-8 GEOTEXTILE AND GEOGRID, 8.5.4 Material the specification has been revised as follows:

8.5.4 Material shall meet the physical property shown in Table 1 and Table 2.

Table 1 – Physical Requirements of *Geogrid Geotextile Fabric*

| Table 1 – I hysical requirements of Geograf Geotextile Fabric | | | | | | |
|---|------------------------------|-----------------|----------------------------------|-------------------------------------|--|--|
| Property | Test | Units | Values - Machine Direction | Values - Cross Machine Direction | | |
| True 1% Tensile Modulus in Use (MD) | ASTM D-6637 | kN/m (lb/ft) | 410 (28,100) | 420 (28,780) | | |
| Junction Strength (MD) | ASTM D-7737 | kN/m (lb/ft) | 21.5 (1,474) | 21.5 (1,474) | | |
| Flexural Stiffness | ASTM D-1388 (Option A) | mg-cm | 750,000 | | | |
| Torsional Stiffness | USACE- Torsional Rigidity | kg- cm/deg | 6.0 | | | |
| Resistance to Installation Damage | ASTM D-5818 | %GP | 71 | | | |
| Resistance to Long Term Degradation | EPA 9090 | % | | 98 | | |
| Ultraviolet Stability (Retained Strength @ 500 hours) | ASTM D-4355 | % | | 98 | | |

Table 2 – Physical Requirements of Geogrid Geotextile Fabric

| Property | Test | Units | Values - Machine Direction | Values - Cross Machine Direction |
|---|-------------|----------|----------------------------------|--|
| Puncture Strength | ASTM D-6241 | kN (lbs) | ≥ 0.47 (105) | |
| Trapezoidal Tear | ASTM D-4533 | kN (lbs) | ≥ 0.51 (115) | ≥ 0.33 (75) |
| Percent Open Area | USACE-02215 | % | | ≤ 15 |
| Apparent Opening Size (AOS) | ASTM D-4751 | US Sieve | ≤ 40 | |
| Permittivity | ASTM D-4491 | Sec-1 | ≤2.1 | |
| Ultraviolet Stability (Retained Strength @ 500 hours) | ASTM D-4355 | % | | ≥ 90 |

3.10.TS-9 OYSTERBREAK UNITS, 9.4.1 <u>Manufacturer Qualifications</u> – the specification has been revised as follows:

Mr. Mike Turley Wayfarer Environmental Technologies, LLC PO Box 11937, New Iberia, LA 70563

Phone: (225) 916-6382 mike@wayfarertech.com http://www.wayfarertech.com/

- 3.11.TS-10 COASTAL HAVEN WAVE ATTENUATION DEVICES (WAD), 10.5.2.1 the specification has been revised as follows:
 - 10.5.1.1 WAD units are constructed of 5,000 psi marine grade concrete reinforced with fibermesh, shall have at least three (3) solid walls, approximately 6.0 4.0 inches thick. WAD walls shall be either smooth or corrugated as shown on the Plans. Walls on the corrugated WADs shall be horizontally corrugated on one face of the WAD and vertically corrugated on back two side walls, as shown on Plans. Walls are to be tapered with lower portion of the WAD®s having an approximate 11.0 foot dimension from projected point to projected point (9.5 foot actual base length), rising 5.0 feet in height to a 4.55 foot table. WADs shall have an open bottom and an enclosed top wall with an opening. Side walls shall have triangular tapered openings. WAD units are to be fabricated as detailed on the Plans.
- 3.12.TS-10 COASTAL HAVEN WAVE ATTENUATION DEVICES (WAD), 10.5.2.1 the specification has been revised as follows:
 - 10.5.2.1 Unit Weight: greater than or equal to 8,000 7,200 lbs and less than 9,150 lbs.
- 3.13. TS-11 REEF BALL UNITS, 11.5.1.3 the specification has been revised as follows:
 - 11.5.1.3 Two hole configurations shall be used. Type 1 will consist of the manufacturer's standard Reef Ball hole pattern utilizing *up to* 22 holes per Reef Ball, *or per manufacturer recommendations and Engineer's approval*. Hole size and location shall be set per manufacturer's instructions. Type 2 will consist of a Reef Ball hole pattern utilizing 4 holes which should be spaced approximately mid-unit high and approximately equally around the unit perimeter.
- 3.14.TS-11 REEF BALL UNITS, 11.5.2.1 the specification has been revised as follows:
 - 11.5.2.1 Unit Weight: greater than or equal to 4,000 3,500 lbs and not to exceed 8,000 lbs.
- 3.15.TS-12 REEFBLK UNITS, 12.3.1 <u>Manufacturer Qualifications</u> the specification has been revised as follows:
 - 12.3.1 <u>Manufacturer Qualifications</u>: Manufacturer shall be Coastal Environments, Inc (CEI) or an approved equal. Engineer must approve equivalent manufacturer 72

hours prior to bid date. CEI contact information:

- 3.16. TS-12 REEFBLK UNITS, 12.7.2 the specification has been revised as follows:
 - 12.7.2 Aggregate shall be #57 #4 crushed limestone.
- 3.17.TS-12 REEFBLK UNITS, 12.19.1 the specification has been revised as follows:
 - 12.19.1 **Reef Ball ReefBLK** Units will be accepted by the Owner based on the in-place condition. It is the responsibility of the Contractor to deliver and install the ReefBLK Units in an undamaged state.
- 3.18. TS-16 COATINGS, 16.9.1.2 the specification has been revised as follows:
 - 16.9.1.2 All surfaces of the round piles and fabrications shall be coated with the coating system specified herein. *Piles do not require coating on the inside.*
- 3.19. TS-16 COATINGS, the following paragraph has been added:
 - 16.9.1.3 Coating is required to an elevation, at a minimum, 5 ft below the mudline for the installed pile.

4. REVISIONS TO THE PLANS

- 4.1. Sheet 22 WAD UNIT DETAILS: Wall thickness on Section A modified to 4" thick wall, typical. Revisions are included in Attachment B.
- 4.2. Sheet 28 OYSTERBREAK LAYOUT: Section A is mirrored to show two pegs of the top Oysterbreak units facing seaward to match Detail 1, and Detail 3 is modified to show revised Oysterbreak spacings. Revisions are included in Attachment B.

Attachment A Mandatory Pre-Bid Conference Attendance Record



LIVING SHORELINE DEMONSTRATION PROJECT,

PROJECT NAME: ST. BERNARD PARISH, LOUISIANA

PROJECT No.: PO-0148

DATE: OCTOBER 20, 2015

LINDY C. BOGGS INTERNATIONAL CONFERENCE CENTER, ROOM 236, UNO, 2045 LAKESHORE DRIVE, NEW ORLEANS,

LOCATION: LA 70122

PROJECT ENGINEER: TYE FITZGERALD, P.E.

PROJECT MANAGER: MICAELA CONER

CONSTRUCTION ENGINEER: DAVID CHAMBERS, P.E.

ENGINEER OF RECORD: JOSH CARTER, P.E.

| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|--------------------------------|------------------------|---|------------------|--------------------------------------|------------------------------|
| Migaela Coner Micaela Coner | | HSD Laurel Ave BR, LA 70802 | 225-342- | micaela.coner@la.sou | of colle |
| Burnard Escoy | marine | 4400 Old Pont Craineston fx. Ad. | 237- 2941483 | MRB. @ collan matina LTD Con | Bind Euge |
| PARELL BENDIT | QUALMY FIRST MARINE | 2160 8 14 St., Suite B MANDEVIlle, & 70471 | 985. 302-9348 | B dbensite Quality FIRST MARINE. Com | Davel Scivil |
| JERRY DEVILLE | MEEKS MARINE | 804 GA:LLE DR Covington, LA 70433 | 985 | JCDEVILLE @ WEEKS MARINE. COM | gry dhow |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-QUT) |
|-----------------------------|--------------------------|--|-----------------|--------------------------------|------------------------------|
| Thomas J BROWN | LSS | Main Street, Suite B | 28 829 N3 | Living Smore line solutions | De fair |
| Brady Richard | TetraTeuh | Butin Street, Suite B Butin Rouge, LA | 223-383 | Brack. Richard e Tetratale com | Rnady Richard |
| Tye Fitzgerald | CPRA | 450 Laurel Ave Baton Rauge, LA | 225-342 | tge fitzgeraldælunger | Su Felican |
| Sustin Merifield | CPRA | Baton Rouge Office | 225-342- | Justin Merrifield @LA. gov | It of |
| Josh Carter Qe | Hatch Moth Mai Donald | GSU Poy Vras ste 2025 New Orlean LA 70130 | 504 383 9785 | josh.cartere hatchmoft.com | Je |
| Joshun Todd fol Zell | Hatch Mott MacDonald | New Orleans LA 70130 | 504 383 9776 | joshua. todd @ hatkh mott. com | fort Tolel |
| Lonnie Dunn | Luhr Bros., In | P.O. Box 7886 Alexandria LA 71306 | 318 | Ionnie@lubralex.com | Ment |
| Tim VESTILE Jew Util | MEEKS MARINE MC. | Alexandria LA 7/306 304 GRILLEDK COVINUTUM, LA 10433 | 985-991 | TOUGSTAL Q WELTS MARING. COM | Tudel |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|---------------------------------|--|-----------------------------|-----------------------------------|------------------------------|
| Danny Delahoussaye | MARRIAN/ DES | LAFAYETTE LA 70508 | 337 856-0034 | danny @ magellan-LLC. com | 7/ |
| Thy Letter | Leblanc Marine | 3001 Rex J. Champagne PO Box 9959 New Iberia, LA 70560 | 337- 364- 4701 | jhyleblanc@leblancmarine.com | Joseph |
| PARKER MCLELLAN | PINE BLUFF SAND & GRAVEL CO. | 2200 LINCOLN AVE | (318) 623 | parker. meclellan epbsgc.com | Mu |
| Demire Outra | Dutia Goop | 2350 Keiner Mid Sv. Fe 200 Son Rafael CA, 94901 | 9115-258 1588 | ddutin à dutingroup.com | Denise Duka |
| MIKE MITSKA | HYDROTERRA | SCOTT, LA 70560 | 337-315 | MIKE. NITSKA@ HYDROTEIUCATEL. CON | Millall |
| TRAVIS CUSIMANO | CATUN MARITIME | 115 CONCORD ST. ABBEVILLE LA, MOSTO | 337-893 3686 | travis. Cusimano@cajunusA.com | Jan June |
| BLAKE DWOSKIN | CAYO, LLC | 1400 EVERTAY PLLY 575 127 FORT WORTH, TX 76140 | 817-568-681 281-530_9114 | , , , , | ALZIL |
| Tylen Orgo | Ecrumones | 1913 Houra Blod. Metailie LA Food | 225 372 5590 | tylereornesturies. com | 7/ |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|----------------------|----------------------------|---------------------------|--|------------------------------|
| Kalph Dioz | Boh Bros | POB 53266 N.O. LA 70153 | 504 | rdiaz @ boh bros. com | Kallhour |
| for the fisher | MAGELLENALS | P.O. BOX 309 | 762/ (837) 924-7444 | -1 014 - 0001 | JR. F. RISS |
| David V. Vaylon | MATTHOUS BRUS | PASS CHRISTIAN, MS 35571 | 228- | ************************************** | David Playla |
| Muri Breche | | | 213/503 | | muri Briche |
| Jun Byga | Reef Imeration | 2415 Mamichal 2415 | 941- | Larry a rectionautims, con | Lom John Com |
| | 1 | 1304 Macorthan Ave | 3519 357 945 | | Cold To-le |
| Richylor Thosodowns | Wiles Recep | PO 50, 253 | 830/ 985 3848770 | tray Quilcomarch buggies. Com | |
| Taylor Roy | Bury Birs CENTAUR | BELLE CHASSE, LA 70037 | 504- 427- 4396 | TAYLOR @ CENTAURLLC. Com | Body Lythalands |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|--------------------------------|--|------------------|--|------------------------------|
| DALE P. ROBICHEAUS | WAYFARER | INTO I BEKING IN | 337 578-1918 | DALF CWAYFARER TECH. COM | Dale Tolaly |
| MIKE | WOYFARER | 101 DOREMUS NEW JBERIA, LA | 916-6382 | MIKECUNYFARERTECH. Com | mike Vula |
| CHELLY STUBIS | 0057 | COUNGTON, M | 985 871-7472 | Shell @ DQSI. con | |
| Stinley Lee | Dasi | 19218 N 542 St Corington, LA 70433 | 813-947-0751 | Stanley @ DQSI. com | |
| Elund Wal | SAV Trucking | 10 34/000 Clelwete, Ld 70043 | 504)99 5090 | , e wood sav trucking & Galler I com - | En l |
| Boogie BAYE | Pontchartrain Partners, LLC | NEW OR (EQUS, LA 70130 | 504-87Z 3199 | boogie.baye@Pontchpartners.com | Milfred of Baye for |
| SAM DAPOFE | DRC EMERGENCY SORVICES | 6258 MARSHAL FORK ST. New Orleans, LA 70129 | 251-232- 3660 | SDANCER DDRCUSA. COM | Me |
| John Troutman | CPR4 | | | | |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|----------------------------|---|--------------------------|---|------------------------------|
| NOUN SIMONEAUF, I. | BERTUCCI GNIMAY | P.O. BOX 10582 JEFFEREN/CA, 70181 | (504) 835-0303 | Molans @ BEETUCCICOP. com | Villey |
| Naw Simoneaux, 111 | BEETUCCI COMMACTINE | (P.O. Box 10582, JEFFERSON, LA 70181 | (5•4) 835-0303 | NOLAN 3 @ BEKENCCICORP.com | 828 |
| LARRY HICKER | Co. | P.O. Box 51778, N.O. CA 20151 | 504 895 0322 | Thecker@buildingspecialtiesoulie. Net | Laury Hechen |
| Darry 1 Countlion J. | | 2160 8th 5t. Mandeville, LA 70471 | 504 909-69 5 9 | doour llien equality first Marine. com | Dary Call M |
| COTEDIA PRIORITAR | Ben Bros Const. Co. LLC | 730 S. TONTE ST. NEW CRLEANS, LA 70119 | (504) 827 7616 | ASALADINO @ BOHBEOS. COM | ANTHONY SALADONS |
| Scott BARNOUSEL | SINGUINT SOUNDUS | 10132 BINDEN DE PLACIDOMA FL 32507 | 850 375 6622 | S BARIKONSKI @ LIC'ING STATIFCING SCRUTIONS. OR | Just J |
| TERRY Songy | PCS | GENNEL, LI | 504- 467- 1444 | terry. Songre posbuilds. com | Dy |
| George Witanova | critanovic fowing | 130 Woodchese Sf Belle Chase, LA 70037 | 504- 452 1153 | george@ evitanovictowing.com | George Critanovic |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|-----------------------------|---|------------------------|-------------------------------------|------------------------------|
| Ryan Littlewood | Coastal Environments, In | | 225 · 383 · 7455 | Plitlewood @ coastaleur.com | BACILI |
| RIGIN MATHE | | V-50 POYDRAS SLITE 2345 V- NO.LA 70130 | 504 872 3199 | ELGIN. MATHIS & Portalpartuers, com | |
| Davidfollette | Pine Bluff | Baton Rouge, LA 70805 | 225 636 0697 | david. follette appsgacom | Wenter |
| | | | | | • |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|-----------------|-----------------|--------------|----------------|------------------------------|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | 9 4 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|-----------------|-----------------|--------------|----------------|------------------------------|
| | | | | | |
| | | | | | |
| | | | | 8 | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



| NAME/SIGNATURE (SIGN-IN) | COMPANY NAME | COMPANY ADDRESS | PHONE NO. | E-MAIL ADDRESS | NAME/SIGNATURE (SIGN-OUT) |
|-----------------------------|-----------------|-----------------|--------------|----------------|------------------------------|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| 8 | | | | | |
| | | | | | |
| | | | | | |
| | | | | | у. |

Attachment B Plan Revisions



